



Mr Alan Turner
21a Stuart House
Cromwell Buisness Park
Chipping Norton
Oxfordshire
OX7 5SR
United Kingdom




QUOTATION





Reference Mr Smith
Quotation Number Q3019
Date of Quotation 1 June 2018
Validity 30 days



Barn Cottage

Dear Sir

Thank you for your valued enquiry, below is a detailed specification for your project. Should you agree with the details please sign and return the order confirmation sheet enclosed with this Quotation. Should you require any changes please contact me when convenient to yourself.

Item (sizes)	Description	Qty	Unit Cost	Total Cost
 <p>1200mm 1200mm</p>	<p>Window - (W1) Kitchen HP Flush Casement Window Friction Hinge - Espag - Brass Handles Timber Type: Best Quality Softwood with Sapele cill Planitherm + 4/16/4 Clear DG Units (Argon) Warm edge spacer One coat of primer only (all other decoration by others) U-value=1.48 50.62 kgs</p>	1	£973.84	£973.84
 <p>1050mm 1150mm</p>	<p>Window - (W2) Study HP Flush Casement Window Friction Hinge - Espag - Brass Handles Timber Type: Best Quality Softwood with Sapele cill Planitherm + 4/16/4 Clear DG Units (Argon) Warm edge spacer One coat of primer only (all other decoration by others) U-value=1.51 41.34 kgs</p>	1	£653.53	£653.53
 <p>1200mm 2100mm</p>	<p>Sliding Sash - (SS1) Lounge Traditional Box Frame - Fully Weatherstripped Cords - Leads - Brass Fittings Timber Type: Best Quality Softwood with Sapele cill Planitherm + 4/16/4 Clear Toughened DG Units with Duplex Bar (Argon) Warm edge spacer One coat of primer only (all other decoration by others) U-value=1.34 244.00 kgs</p>	2	£1,306.83	£2,613.66
Carried Forward				£4,241.03

Item (sizes)	Description	Qty	Unit Cost	Total Cost
		Brought Forward		£4,241.03
	Sliding Sash - (SS2) Hall Traditional Box Frame - Fully Weatherstripped Cords - Leads - Brass Fittings Timber Type: Best Quality Softwood with Sapele cill Planitherm + 4/16/4 Clear DG Units (Argon) Warm edge spacer Planitherm + 4/16/4 Clear Toughened DG Units (Argon) Warm edge spacer One coat of primer only (all other decoration by others) U-value=1.38 66.20 kgs	1	£1,454.55	£1,454.55
	Door - (D1) Utility Room 44mm Flush Door / Hung in Door Lining Door Factory Hung - Fitted With Stainless Butt Hinges Timber Type: European Oak Door Blank: Sentry Prolite Door Blank 44mm Outside Veneer: Ash Crown Veneer Glass: 4mm Clear Toughened 2 Coats Osmo Finishing Oil 77.16 kgs	1	£684.01	£684.01
	Door - (DD1) Dinning Room Standard Door 56mm thick Door Factory Hung - Fitted With 5 Lever Lock Timber Type: European Oak Planitherm + 4/16/4 Clear Toughened DG Units with Duplex Bar (Argon) Warm edge spacer 2 Coats Osmo Finishing Oil U-value=1.83 133.92 kgs	1	£1,908.03	£1,908.03
Screen - (SC1) Entrance Hall Flush Casement Frame - High Performance Timber Type: European Oak Planitherm + 4/16/4 Clear Toughened DG Units (Argon) Warm edge spacer 2 Coats Osmo Finishing Oil U-value=1.79 240.28 kgs		1	£4,539.97	£4,539.97
	Door 54mm External Open in Door - Ovolo Mould - Rebated for 24mm D/G Units Door Factory Hung - Fitted With 5 Lever Lock Timber Type: European Oak Planitherm + 4/16/4 Clear Toughened DG Units with Duplex Bar (Argon) Warm edge spacer 2 Coats Osmo Finishing Oil Casement Flush Casement 54mm Thick Friction Hinge - Espag - Brass Handles Timber Type: European Oak Planitherm + 4/16/4 Clear Toughened DG Units with Duplex Bar (Argon) Warm edge spacer 2 Coats Osmo Finishing Oil			
		Carried Forward		£12,827.59

Item (sizes)	Description	Qty	Unit Cost	Total Cost
Brought Forward				£12,827.59
900mm 1650mm 	Gothic Window - WG1 Fixed Casement - Ovolo Mould Timber Type: European Oak 2 Coats Osmo Finishing Oil	1	£1,169.14	£1,169.14
1500mm 480mm 	Furniture Depth = 600mm Coffee Table Timber Type: European Oak	1	£657.00	£657.00
Delivery to Chipping Norton				£160.00
				<hr/> £14,813.73
VAT @ 20%				£2,962.75
Total				£17,776.48
Deposit enclosed to confirm order...				£7,110.59
Balance				£10,665.89
Additional Items not including VAT				
Installation 5 days x 2 men @ £300.00 a day				£1,500.00

Total Weight 853.53 kgs

NOTES:

Diagrams of windows, doors and frames indicate style viewed from the outside and do not reflect size. All weights shown on this document are approximate and are intended to assist in manual handling considerations.

I accept the above details are correct and enclose my deposit.....

Please sign here.

There are over 20 customisable estimate/quotation templates to allow user flexibility.

"We have won extra work due to the speed, accuracy and professionalism of JMS"